Sl. No.	Items of work	Unit	Rate in words	Rate in figures	Quantity	Cost
				Rs. a. p.		
12	Rounding off corners at the junction of parapets in the roofing.	R.ft.			190	
13	Applying carbolastic to the cracks of the terrace.	Lump			sum	
	Removing the roots of green plants on the roofing by applying Atlas weed killer.	Lump			sum	
15	Repairing the images of lines at corners	Lump			sum	
16	Rough stone pitching 3 miles lead ...	C.yd.			69	
	Improving and extending the Chandrasala.					
1	Dismantling the side walls, lowering the roof slabs and removing steps and pillars.	Lump			sum	
2	Earthwork excavation ...	C.yd.			26	
3	Jelly concrete in chunam mortar ...	C.ft.			560	
4	Burnt stone in chunam mortar with bond slabs at an interval of 2'.	"			889	
5	Ornamental brick parapets 2½ feet high with plastering.	R.ft.			65½	
6	Burnt stone slabs 6" to be roughly dressed set in mortar.	S.ft.			333	
7	Burnt stone slabs 6" dressed new ...	"			848	
8	Cut stone pillars with bases and capitals	C.ft.			57	
9	Cut stone beams	"			93	
10	Plastering with chunam mortar ...	Sqr.			4·50	
11	Pointing with cement	"			16·87	
	Improving and extending Mahadwaram.					
1	Dismantling the present mud walls removing old slabs and using them to Chandrasala.	Lump			sum	
2	Earthwork excavation	C.yd.			18	
3	Jelly concrete in chunam mortar ...	C.ft.			357	
4	Burnt stone in chunam mortar with bond slabs at an interval of 2 feet.	C.ft.			977	
5	Ornamental brick parapet 2½ feet high with plastering.	R.ft.			64	
6	Burnt stone slabs 6" thick dressed ...	S.ft.			676	
7	Cut stone pillars with bases and capitals	C.ft.			22½	
8	Cut stone beams	"			50	
9	Teakwood door shutters 3" thick straps and hinges, etc., complete with chacolate painting.	S.ft.			34	
10	Plastering with chunam mortar ...	Sqr.			2·40	
11	Pointing with cement	"			13·08	
12	Extending the compound wall by the side of Mahadwara and unforseen charges.	Lump			sum	

A. TANDONI RAO,
Executive Engineer.

MYSORE DIVISION, MYSORE.

Dated 21st November 1930.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 15th December 1930, for constructing two additional rooms in the Taluk Cutchery at Malvalli. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore between the office hours.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes as earnest money and be superscribed "Tender for constructing two additional rooms in the Taluk Cutchery at Malvalli" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tendered rate will not be increased on any account afterwards.

10. Rates should be entered both in figures and words for each item of work.

11. Lumpsum estimates at per cent above or below the sanctioned amount will not be accepted.

Abstract estimate for constructing two additional rooms at the wings of Taluk Office, Malvalli.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		
1	Earthwork excavating to foundation ..	C.yds.		27	
2	Stone jelly in line mortar ...	C.ft.		225	
3	Burnt brick in mortar ...	"		877	
4	Do clay ...	"		856	
(a)	Do chunam ...	"		187	
5	Burnt stone slabs dressed and fined 6" thick ...	S.ft.		234	
6	Chunnam plastering ...	Sqr.		20·08	
7	Whitewashing two coats ...	"		24·61	
8	Cut stone pillers with bases and capitals 7½' ...	Each		4	
9	Teak wood wrought and put up ...	C.ft.		55·54	
10	Wood oiling ...	Sqr.		4	
11	Digging wall for fixing rafters with tarring ...	Lump		sum	
12	Teakwood pannelled door with hinges, etc., complete.	S.ft.		72	
13	Teakwood pannelled windows with iron bars, pannelled shutters on one side and glazed shutters inside.	"		63	
14	Teakwood glazed ventilators with iron bars, etc., complete.	"		5	
15	Chacolate painting ...	Sqr.		2·45	
16	Roofing with Bengal terrace with 6" course of flat tiles laid on mortar over 1½" thick reepers and plastering at top.	"		1·46	
17	Roofing with pucca terrace 10" thick and plastering at top and bottom complete.	"		4·08	
18	Brick in chunam cornice 9" x 9" plastering, etc., complete.	R.ft.		81	
19	Burnt brick in chunam parapet walls with pillastera ¾ x 1½' high plastering complete with cornice at top.	"		83	
20	Filling in basement clearing site, etc., constructing parapets step, etc., complete.	Lump		sum	